BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/22/2020-21, Date:17.11.2020

SCHEDULE-B

NAME OF WORK:Maintenance of roads and footpath in ward no 12 Shettyhalli

| Sl. No | Description of work | Unit | Qty | Rates Quoted by Contractor MANIKANTA M V | |
|---|---|---|---|---|---|
| | | | | In Figures (Rs.) | In Words (Rs.) |
| 1 | 2 | 3 | 4 | 5 | 6 |
| 1 | Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. etc., complete as per specifications and as per the direction of Engineer-in-charge of the work. | Cum | 132.00 | 175.0 | Rupees One Hundred Seventy Five Only |
| 2 | Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregtes @ 0.56cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM etc., complete as per specifications and as per the direction of Engineer-in-charge of the work. | Cum | 18.00 | 4286.0 | Rupees Four Thousand Two Hundred Eighty Six Only |
| | Providing and laying Design mix M25 with OPC @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.7cum and fine aggregates @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 - i) Upto 5m height etc., complete as per specifications and as per the direction of Engineer-in-charge of the work. | Cum | 151.20 | 4332.0 | Rupees Four Thousand Three Hundred Thirty Two Only |
| | Providing TMT teel reinforcement for RCC work including starightening, cutting, bending, hooking, placing in position, lapping and /or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design( laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification | Tonne | 4.31 | 56418.00 | Rupees Fifty Six Thousand Four Hundred Eighteen Only |

Scanned by CamScanner

| | | | | | |
|---|---|---|---|---|---|
| | ing and fixing precast reinforced cement concrete ng slabs 10cm thick made out of M25 with OPC emnt @340kgs per cum, 20mm and down size graded anite metal corse aggreates @0.70 cm and fine aggregates 0.74 cum with super plasticizers machine mixed, including providing and removing centering, shuttering strutting propping etc., for edges of slab with TMT steel (Fe500) cost & reinforcement charges including finishing as required with cost of reinforcement etc., complete as per specifications and as per the direction of Engineer-in-charge of the work. | Sqm | 108.00 | 1211.0 | Rupees One Thousand Two Hundred Eleven Only |
| 6 | Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete as per specifications and as per the direction of Engineer-in-charge of the work. | Nos | 636.00 | 324.0 | Rupees Three Hundred Twenty Four Only |
| 7 | Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 etc., complete as per specifications and as per the direction of Engineer-in-charge of the work. | Sqm | 45.00 | 64.0 | Rupees Sixty Four Only |

gnature of the Contractor

Executive Engineer
Dasarahalli Division
Dasarahalli Division, Bengaluru-73

Scanned by CamScanner